



Zone Sizing Summary for ADM GUARDA MUNIC

Project Name: CENTRO INTEG, SEGURANÇA PÚBLICA DE HORIZONTE rev01

05/09/2022

Prepared by: José Mendonça Filho Segundo

Air System Information

Air System Name ADM GUARDA MUNIC
Equipment Class SPLT AHU
Air System Type SZCAV

Number of zones 1
Floor Area 22,7 m²
Location Fortaleza, Brazil

Sizing Calculation Information

Calculation Months Jan to Dec
Sizing Data Calculated

Zone L/s Sizing Sum of space airflow rates
Space L/s Sizing Individual peak space loads

Zone Sizing Data

Zone Name	Maximum Cooling Sensible (kW)	Design Airflow (L/s)	Minimum Airflow (L/s)	Time of Peak Load	Maximum Heating Load (kW)	Zone Floor Area (m ²)	Zone L/(s-m ²)
Zone 1	3,1	271	271	Feb 1400	0,0	22,7	11,93

Zone Terminal Sizing Data

No Zone Terminal Sizing Data required for this system.

Space Loads and Airflows

Zone Name / Space Name	Mult.	Cooling Sensible (kW)	Time of Load	Air Flow (L/s)	Heating Load (kW)	Floor Area (m ²)	Space L/(s-m ²)
Zone 1							
ADM GUARDA MUNIC.	1	3,1	Feb 1400	271	0,0	22,7	11,93

Ventilation Sizing Summary for ADM GUARDA MUNIC

Project Name: CENTRO INTEG. SEGURANÇA PÚBLICA DE HORIZONTErev01
 Prepared by: José Mendonça Filho Segundo
 05/09/2022 08:24

1. Summary
 Ventilation Sizing Method
 Design Ventilation Airflow Rate 68 L/s

2. Space Ventilation Analysis Table

Zone Name / Space Name	Mult.	Floor Area (m²)	Maximum Occupants	Maximum Supply Air (L/s)	Required Outdoor Air (L/s/person)	Required Outdoor Air (L/s-m²)	Required Outdoor Air (L/s)	Required Outdoor Air (% of supply)	Uncorrected Outdoor Air (L/s)
Zone 1	1	22.7	9.0	270.9	7.50	0.00	0.0	0.0	67.5
ADM GUARDA MUNIC.				270.9					67.5
Totals (incl. Space Multipliers)									

Handwritten signature/initials.



Air System Design Load Summary for ADM GUARDA MUNIC

Project Name: CENTRO INTEG, SEGURANÇA PÚBLICA DE HORIZONTErev01

05/09/2022

Prepared by: José Mendonça Filho Segundo



ZONE LOADS	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Feb 1300			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 31,5 °C / 25,4 °C			HEATING OA DB / WB 22,2 °C / 15,6 °C		
	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	2 m²	330	-	2 m²	-	-
Wall Transmission	15 m²	621	-	15 m²	0	-
Roof Transmission	0 m²	0	-	0 m²	0	-
Window Transmission	2 m²	102	-	2 m²	0	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	23 m²	0	-	23 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	50 m²	771	-	50 m²	0	-
Overhead Lighting	363 W	278	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	500 W	500	-	0	0	-
People	9	458	541	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	0% / 0%	0	0	0%	0	0
>> Total Zone Loads	-	3061	541	-	0	0
Zone Conditioning	-	3154	541	-	0	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Return Fan Load	271 L/s	0	-	271 L/s	0	-
Ventilation Load	68 L/s	564	1442	68 L/s	-90	0
Supply Fan Load	271 L/s	0	-	271 L/s	0	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	3718	1983	-	-90	0
Central Cooling Coil	-	3718	1983	-	-90	0
>> Total Conditioning	-	3718	1983	-	-90	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

Zone Sizing Summary for ADM TRÁNSITO

Project Name: CENTRO INTEG, SEGURANÇA PÚBLICA DE HORIZONTErev01

05/09/2022

Prepared by: José Mendonça Filho Segundo



Air System Information

Air System Name ADM TRÁNSITO
 Equipment Class SPLT AHU
 Air System Type SZCAV

Number of zones 1
 Floor Area 26,7 m²
 Location Fortaleza, Brazil

Sizing Calculation Information

Calculation Months Jan to Dec
 Sizing Data Calculated

Zone L/s Sizing Sum of space airflow rates
 Space L/s Sizing Individual peak space loads

Zone Sizing Data

Zone Name	Maximum Cooling Sensible (kW)	Design Airflow (L/s)	Minimum Airflow (L/s)	Time of Peak Load	Maximum Heating Load (kW)	Zone Floor Area (m²)	Zone L/(s-m²)
Zone 1	4,2	369	369	Dec 1600	0,0	26,7	13,81

Zone Terminal Sizing Data

No Zone Terminal Sizing Data required for this system.

Space Loads and Airflows

Zone Name / Space Name	Mult.	Cooling Sensible (kW)	Time of Load	Air Flow (L/s)	Heating Load (kW)	Floor Area (m²)	Space L/(s-m²)
Zone 1							
ADM TRÁNSITO	1	4,2	Dec 1600	369	0,0	26,7	13,81

Ventilation Sizing Summary for ADM TRÁNSITO

Project Name: CENTRO INTEG. SEGURANÇA PÚBLICA DE HORIZONTE Rev01
 Prepared by: José Mendonça Filho Segundo
 05/09/2022 08:24

1. Summary
 Ventilation Sizing Method
 Design Ventilation Airflow Rate 68 L/s

2. Space Ventilation Analysis Table

Zone Name / Space Name	Mult.	Floor Area (m²)	Maximum Occupants	Maximum Supply Air (L/s)	Required Outdoor Air (L/s/person)	Required Outdoor Air (L/s-m²)	Required Outdoor Air (L/s)	Required Outdoor Air (% of supply)	Uncorrected Outdoor Air (L/s)
Zone 1									
ADM TRÁNSITO	1	26.7	9.0	368.7	7.50	0.00	0.0	0.0	67.5
Totals (incl. Space Multipliers)				368.7					67.5



Air System Design Load Summary for ADM TRANSITO

Project Name: CENTRO INTEG, SEGURANÇA PÚBLICA DE HORIZONTErev01

05/09/2022

Prepared by: José Mendonça Filho Segundo

08/24

ZONE LOADS	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Dec 1500			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 31,7 °C / 25,6 °C			HEATING OA DB / WB 22,2 °C / 15,6 °C		
	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	8 m²	1623	-	8 m²	-	-
Wall Transmission	20 m²	867	-	20 m²	0	-
Roof Transmission	0 m²	0	-	0 m²	0	-
Window Transmission	8 m²	378	-	8 m²	0	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	27 m²	0	-	27 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	0 m²	0	-	0 m²	0	-
Overhead Lighting	427 W	340	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	500 W	500	-	0	0	-
People	9	482	541	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	0% / 0%	0	0	0%	0	0
>> Total Zone Loads	-	4190	541	-	0	0
Zone Conditioning	-	4229	541	-	0	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Return Fan Load	369 L/s	0	-	369 L/s	0	-
Ventilation Load	68 L/s	552	1474	68 L/s	-90	0
Supply Fan Load	369 L/s	0	-	369 L/s	0	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	4781	2015	-	-90	0
Central Cooling Coil	-	4781	2016	-	-90	0
>> Total Conditioning	-	4781	2016	-	-90	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		



Zone Sizing Summary for ALOJAMENTO FEMININO

Project Name: CENTRO INTEG, SEGURANÇA PÚBLICA DE HORIZONTErev01

05/09/2022

Prepared by: José Mendonça Filho Segundo

Air System Information

Air System Name **ALOJAMENTO FEMININO**
Equipment Class **SPLT AHU**
Air System Type **SZCAV**

Number of zones **1**
Floor Area **41,3** m²
Location **Fortaleza, Brazil**

Sizing Calculation Information

Calculation Months **Jan to Dec**
Sizing Data **Calculated**

Zone L/s Sizing **Sum of space airflow rates**
Space L/s Sizing **Individual peak space loads**

Zone Sizing Data

Zone Name	Maximum Cooling Sensible (kW)	Design Airflow (L/s)	Minimum Airflow (L/s)	Time of Peak Load	Maximum Heating Load (kW)	Zone Floor Area (m ²)	Zone L/(s-m ²)
Zone 1	3,7	328	328	Feb 1600	0,0	41,3	7,93

Zone Terminal Sizing Data

No Zone Terminal Sizing Data required for this system.

Space Loads and Airflows

Zone Name / Space Name	Mult.	Cooling Sensible (kW)	Time of Load	Air Flow (L/s)	Heating Load (kW)	Floor Area (m ²)	Space L/(s-m ²)
Zone 1							
ALOJAMENTO FEM	1	3,7	Feb 1600	328	0,0	41,3	7,93

Ventilation Sizing Summary for ALOJAMENTO FEMININO

05/09/2022
08:24

Project Name: CENTRO INTEG. SEGURANÇA PÚBLICA DE HORIZONTE rev01
Prepared by: José Mendonça Filho Segundo

1. Summary
Ventilation Sizing Method
Design Ventilation Airflow Rate 90 L/s

2. Space Ventilation Analysis Table

Zone Name / Space Name	Mult.	Floor Area (m²)	Maximum Occupants	Maximum Supply Air (L/s)	Required Outdoor Air (L/s/person)	Required Outdoor Air (L/s-m²)	Required Outdoor Air (L/s)	Required Outdoor Air (% of supply)	Uncorrected Outdoor Air (L/s)
Zone 1	1	41.3	12.0	327.7	7.50	0.00	0.0	0.0	90.0
ALOJAMENTO FEM				327.7					90.0
Totals (incl. Space Multipliers)									



Air System Design Load Summary for ALOJAMENTO FEMININO

Project Name: CENTRO INTEG, SEGURANÇA PÚBLICA DE HORIZONTE rev01

05/09/2022

Prepared by: José Mendonça Filho Segundo



ZONE LOADS	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 1600			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 32,0 °C / 25,5 °C			HEATING OA DB / WB 22,2 °C / 15,6 °C		
	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	2 m²	139	-	2 m²	-	-
Wall Transmission	8 m²	206	-	8 m²	0	-
Roof Transmission	41 m²	860	-	41 m²	0	-
Window Transmission	2 m²	111	-	2 m²	0	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	41 m²	0	-	41 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	58 m²	936	-	58 m²	0	-
Overhead Lighting	661 W	535	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	250 W	250	-	0	0	-
People	12	616	422	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	0% / 0%	0	0	0%	0	0
>> Total Zone Loads	-	3652	422	-	0	0
Zone Conditioning	-	3782	422	-	0	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Return Fan Load	328 L/s	0	-	328 L/s	0	-
Ventilation Load	90 L/s	813	1987	90 L/s	-120	0
Supply Fan Load	328 L/s	0	-	328 L/s	0	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	4595	2410	-	-120	0
Central Cooling Coil	-	4595	2410	-	-120	0
>> Total Conditioning	-	4595	2410	-	-120	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		



Zone Sizing Summary for ALOJAMENTO MASCULINO

Project Name: CENTRO INTEG, SEGURANÇA PÚBLICA DE HORIZONTErev01

05/09/2022

Prepared by: José Mendonça Filho Segundo

08.24

Air System Information

Air System Name **ALOJAMENTO MASCULINO**
Equipment Class **SPLT AHU**
Air System Type **SZCAV**

Number of zones **1**
Floor Area **45,8** m²
Location **Fortaleza, Brazil**

Sizing Calculation Information

Calculation Months **Jan to Dec**
Sizing Data **Calculated**

Zone L/s Sizing **Sum of space airflow rates**
Space L/s Sizing **Individual peak space loads**

Zone Sizing Data

Zone Name	Maximum Cooling Sensible (kW)	Design Airflow (L/s)	Minimum Airflow (L/s)	Time of Peak Load	Maximum Heating Load (kW)	Zone Floor Area (m ²)	Zone L/(s·m ²)
Zone 1	4,6	404	404	Apr 1600	0,0	45,8	8,82

Zone Terminal Sizing Data

No Zone Terminal Sizing Data required for this system.

Space Loads and Airflows

Zone Name / Space Name	Mult.	Cooling Sensible (kW)	Time of Load	Air Flow (L/s)	Heating Load (kW)	Floor Area (m ²)	Space L/(s·m ²)
Zone 1							
ALOJAMENTO MASC	1	4,6	Apr 1600	404	0,0	45,8	8,82

Handwritten signature and initials.

Ventilation Sizing Summary for ALOJAMENTO MASCULINO

05/09/2022
08:24

Project Name: CENTRO INTEG. SEGURANÇA PÚBLICA DE HORIZONTE rev01
Prepared by: José Mendonça Filho Segundo

1. Summary
Ventilation Sizing Method
Design Ventilation Airflow Rate
Sum of Space OA Airflows 120 L/s

2. Space Ventilation Analysis Table

Zone Name / Space Name	Mult.	Floor Area (m²)	Maximum Occupants	Maximum Supply Air (L/s)	Required Outdoor Air (L/s/person)	Required Outdoor Air (L/s-m²)	Required Outdoor Air (L/s)	Required Outdoor Air (% of supply)	Uncorrected Outdoor Air (L/s)
Zone 1	1	45.8	16.0	403.9	7.50	0.00	0.0	0.0	120.0
ALOJAMENTO MASC				403.9					120.0
Totals (incl. Space Multipliers)									



Air System Design Load Summary for ALOJAMENTO MASCULINO

Project Name: CENTRO INTEG, SEGURANÇA PÚBLICA DE HORIZONTE rev01

05/09/2022

Prepared by: José Mendonça Filho Segundo



ZONE LOADS	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Feb 1500			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 32,2 °C / 25,6 °C			HEATING OA DB / WB 22,2 °C / 15,6 °C		
	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	5 m²	366	-	5 m²	-	-
Wall Transmission	10 m²	237	-	10 m²	0	-
Roof Transmission	46 m²	947	-	46 m²	0	-
Window Transmission	5 m²	224	-	5 m²	0	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	46 m²	0	-	46 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	62 m²	990	-	62 m²	0	-
Overhead Lighting	733 W	583	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	250 W	250	-	0	0	-
People	16	804	563	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	0% / 0%	0	0	0%	0	0
>> Total Zone Loads	-	4401	563	-	0	0
Zone Conditioning	-	4490	563	-	0	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Return Fan Load	404 L/s	0	-	404 L/s	0	-
Ventilation Load	120 L/s	1094	2520	120 L/s	-160	0
Supply Fan Load	404 L/s	0	-	404 L/s	0	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	5584	3083	-	-160	0
Central Cooling Coil	-	5584	3083	-	-160	0
>> Total Conditioning	-	5584	3083	-	-160	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

Handwritten signature and initials.



Zone Sizing Summary for ATENDIMENTO

Project Name: CENTRO INTEG, SEGURANÇA PÚBLICA DE HORIZONTE rev01

05/09/2022

Prepared by: José Mendonça Filho Segundo

Air System Information

Air System Name **ATENDIMENTO**
Equipment Class **SPLT AHU**
Air System Type **SZCAV**

Number of zones **1**
Floor Area **26,0** m²
Location **Fortaleza, Brazil**

Sizing Calculation Information

Calculation Months **Jan to Dec**
Sizing Data **Calculated**

Zone L/s Sizing **Sum of space airflow rates**
Space L/s Sizing **Individual peak space loads**

Zone Sizing Data

Zone Name	Maximum Cooling Sensible (kW)	Design Airflow (L/s)	Minimum Airflow (L/s)	Time of Peak Load	Maximum Heating Load (kW)	Zone Floor Area (m ²)	Zone L/(s-m ²)
Zone 1	2,3	205	205	Dec 1400	0,0	26,0	7,89

Zone Terminal Sizing Data

No Zone Terminal Sizing Data required for this system.

Space Loads and Airflows

Zone Name / Space Name	Mult.	Cooling Sensible (kW)	Time of Load	Air Flow (L/s)	Heating Load (kW)	Floor Area (m ²)	Space L/(s-m ²)
Zone 1							
ATENDIMENTO	1	2,3	Dec 1400	205	0,0	26,0	7,89

Handwritten signature and initials.

Ventilation Sizing Summary for ATENDIMENTO

Project Name: CENTRO INTEG. SEGURANÇA PÚBLICA DE HORIZONTE rev01
 Prepared by: José Mendonça Filho Segundo

05/09/2022
 08:24

1. Summary
 Ventilation Sizing Method
 Design Ventilation Airflow Rate 68 L/s

2. Space Ventilation Analysis Table

Zone Name / Space Name	Mult.	Floor Area (m²)	Maximum Occupants	Maximum Supply Air (L/s)	Required Outdoor Air (L/s/person)	Required Outdoor Air (L/s-m²)	Required Outdoor Air (L/s)	Required Outdoor Air (% of supply)	Uncorrected Outdoor Air (L/s)
Zone 1									
ATENDIMENTO	1	26.0	9.0	205.2	7.50	0.00	0.0	0.0	67.5
Totals (incl. Space Multipliers)				205.2					67.5



Air System Design Load Summary for ATENDIMENTO

Project Name: CENTRO INTEG, SEGURANÇA PÚBLICA DE HORIZONTE Rev01

05/09/2022

Prepared by: José Mendonça Filho Segundo



ZONE LOADS	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Dec 1400			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 31,5 °C / 25,5 °C			HEATING OA DB / WB 22,2 °C / 15,6 °C		
	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	3 m²	534	-	3 m²	-	-
Wall Transmission	5 m²	261	-	5 m²	0	-
Roof Transmission	0 m²	0	-	0 m²	0	-
Window Transmission	3 m²	133	-	3 m²	0	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	26 m²	0	-	26 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	42 m²	242	-	42 m²	0	-
Overhead Lighting	416 W	325	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	300 W	300	-	0	0	-
People	9	537	712	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	0% / 0%	0	0	0%	0	0
>> Total Zone Loads	-	2333	712	-	0	0
Zone Conditioning	-	2441	712	-	0	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Return Fan Load	205 L/s	0	-	205 L/s	0	-
Ventilation Load	68 L/s	557	1400	68 L/s	-90	0
Supply Fan Load	205 L/s	0	-	205 L/s	0	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	2998	2112	-	-90	0
Central Cooling Coil	-	2998	2112	-	-90	0
>> Total Conditioning	-	2998	2112	-	-90	0
Key:	Positive values are ckg loads Negative values are htg loads			Positive values are htg loads Negative values are ckg loads		

Handwritten signature/initials.

Zone Sizing Summary for BALCÃO DE ATENDIMENTO

Project Name: CENTRO INTEG, SEGURANÇA PÚBLICA DE HORIZONTE rev01

05/09/2022

Prepared by: José Mendonça Filho Segundo



Air System Information

Air System Name **BALCÃO DE ATENDIMENTO**
 Equipment Class **SPLT AHU**
 Air System Type **SZCAV**

Number of zones **1**
 Floor Area **26,2** m²
 Location **Fortaleza, Brazil**

Sizing Calculation Information

Calculation Months **Jan to Dec**
 Sizing Data **Calculated**

Zone L/s Sizing **Sum of space airflow rates**
 Space L/s Sizing **Individual peak space loads**

Zone Sizing Data

Zone Name	Maximum Cooling Sensible (kW)	Design Airflow (L/s)	Minimum Airflow (L/s)	Time of Peak Load	Maximum Heating Load (kW)	Zone Floor Area (m ²)	Zone L/(s-m ²)
Zone 1	4,0	352	352	Feb 1600	0,0	26,2	13,43

Zone Terminal Sizing Data

No Zone Terminal Sizing Data required for this system.

Space Loads and Airflows

Zone Name / Space Name	Mult.	Cooling Sensible (kW)	Time of Load	Air Flow (L/s)	Heating Load (kW)	Floor Area (m ²)	Space L/(s-m ²)
Zone 1							
BALCÃO DE ATENDIMENTO	1	4,0	Feb 1600	352	0,0	26,2	13,43

Handwritten signature and initials.

Ventilation Sizing Summary for BALCAO DE ATENDIMENTO

Project Name: CENTRO INTEG. SEGURANÇA PÚBLICA DE HORIZONTE rev01
 Prepared by: José Mendonça Filho Segundo
 05/09/2022 08:24

1. Summary
 Ventilation Sizing Method
 Design Ventilation Airflow Rate 30 L/s

2. Space Ventilation Analysis Table

Zone Name / Space Name	Mult.	Floor Area (m²)	Maximum Occupants	Maximum Supply Air (L/s)	Required Outdoor Air (L/s/person)	Required Outdoor Air (L/s-m²)	Required Outdoor Air (L/s)	Required Outdoor Air (% of supply)	Uncorrected Outdoor Air (L/s)
Zone 1									
BALCAO DE ATENDIMENTO	1	26,2	4,0	351,8	7,50	0,00	0,0	0,0	30,0
Totals (incl. Space Multipliers)				351,8					30,0





Air System Design Load Summary for BALCAO DE ATENDIMENTO

Project Name: CENTRO INTEG, SEGURANÇA PÚBLICA DE HORIZONTErev01

05/09/2022

Prepared by: José Mendonça Filho Segundo

08:24

ZONE LOADS	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Feb 1300			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 31,5 °C / 25,4 °C			HEATING OA DB / WB 22,2 °C / 15,6 °C		
	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	0 m²	0	-	0 m²	-	-
Wall Transmission	9 m²	363	-	9 m²	0	-
Roof Transmission	0 m²	0	-	0 m²	0	-
Window Transmission	0 m²	0	-	0 m²	0	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	26 m²	0	-	26 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	43 m²	256	-	43 m²	0	-
Overhead Lighting	419 W	321	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	2840 W	2840	-	0	0	-
People	4	203	240	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	0% / 0%	0	0	0%	0	0
>> Total Zone Loads	-	3984	240	-	0	0
Zone Conditioning	-	4158	240	-	0	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Return Fan Load	352 L/s	0	-	352 L/s	0	-
Ventilation Load	30 L/s	249	695	30 L/s	-40	0
Supply Fan Load	352 L/s	0	-	352 L/s	0	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	4407	935	-	-40	0
Central Cooling Coil	-	4407	935	-	-40	0
>> Total Conditioning	-	4407	935	-	-40	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

Zone Sizing Summary for CORREGEDORIA

Project Name: CENTRO INTEG, SEGURANÇA PÚBLICA DE HORIZONTErev01
05/09/2022

Prepared by: José Mendonça Filho Segundo

08:24



Air System Information

Air System Name **CORREGEDORIA**
Equipment Class **SPLT AHU**
Air System Type **SZCAV**

Number of zones **1**
Floor Area **15,8 m²**
Location **Fortaleza, Brazil**

Sizing Calculation Information

Calculation Months **Jan to Dec**
Sizing Data **Calculated**

Zone L/s Sizing **Sum of space airflow rates**
Space L/s Sizing **Individual peak space loads**

Zone Sizing Data

Zone Name	Maximum Cooling Sensible (kW)	Design Airflow (L/s)	Minimum Airflow (L/s)	Time of Peak Load	Maximum Heating Load (kW)	Zone Floor Area (m²)	Zone L/(s-m²)
Zone 1	1,8	157	157	Feb 1400	0,0	15,8	9,97

Zone Terminal Sizing Data

No Zone Terminal Sizing Data required for this system.

Space Loads and Airflows

Zone Name / Space Name	Mult.	Cooling Sensible (kW)	Time of Load	Air Flow (L/s)	Heating Load (kW)	Floor Area (m²)	Space L/(s-m²)
Zone 1							
CORREGEDORIA	1	1,8	Feb 1400	157	0,0	15,8	9,97

[Handwritten signatures and marks]

Ventilation Sizing Summary for CORREGEDORIA

05/09/2022
08:24

Project Name: CENTRO INTEG, SEGURANÇA PÚBLICA DE HORIZONTErev01
Prepared by: José Mendonça Filho Segundo

1. Summary
Ventilation Sizing Method
Design Ventilation Airflow Rate 23 L/s

2. Space Ventilation Analysis Table

Zone Name / Space Name	Mult.	Floor Area (m²)	Maximum Occupants	Maximum Supply Air (L/s)	Required Outdoor Air (L/s/person)	Required Outdoor Air (L/s-m²)	Required Outdoor Air (L/s)	Required Outdoor Air (% of supply)	Uncorrected Outdoor Air (L/s)
Zone 1	1	15.8	3.0	157.5	7.50	0.00	0.0	0.0	22.5
CORREGEDORIA									22.5
Totals (incl. Space Multipliers)				167.5					22.5



Air System Design Load Summary for CORREGEDORIA

Project Name: CENTRO INTEG, SEGURANÇA PÚBLICA DE HORIZONTE rev01

05/09/2022

Prepared by: José Mendonça Filho Segundo



	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Feb 1300			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 31,5 °C / 25,4 °C			HEATING OA DB / WB 22,2 °C / 15,6 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	2 m²	330	-	2 m²	-	-
Wall Transmission	5 m²	196	-	5 m²	0	-
Roof Transmission	0 m²	0	-	0 m²	0	-
Window Transmission	2 m²	102	-	2 m²	0	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	16 m²	0	-	16 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	32 m²	503	-	32 m²	0	-
Overhead Lighting	253 W	194	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	300 W	300	-	0	0	-
People	3	153	180	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	0% / 0%	0	0	0%	0	0
>> Total Zone Loads	-	1778	180	-	0	0
Zone Conditioning	-	1867	180	-	0	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Return Fan Load	157 L/s	0	-	157 L/s	0	-
Ventilation Load	23 L/s	190	516	23 L/s	-30	0
Supply Fan Load	157 L/s	0	-	157 L/s	0	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	2058	696	-	-30	0
Central Cooling Coil	-	2058	696	-	-30	0
>> Total Conditioning	-	2058	696	-	-30	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

Handwritten signature and initials.

Zone Sizing Summary for JUNTA DE RECURSOS

Project Name: CENTRO INTEG, SEGURANÇA PÚBLICA DE HORIZONTE rev01

05/09/2022

Prepared by: José Mendonça Filho Segundo

08:24

Air System Information

Air System Name **JUNTA DE RECURSOS**
Equipment Class **SPLT AHU**
Air System Type **SZCAV**

Number of zones **1**
Floor Area **14,9 m²**
Location **Fortaleza, Brazil**

Sizing Calculation Information

Calculation Months **Jan to Dec**
Sizing Data **Calculated**

Zone L/s Sizing **Sum of space airflow rates**
Space L/s Sizing **Individual peak space loads**

Zone Sizing Data

Zone Name	Maximum Cooling Sensible (kW)	Design Airflow (L/s)	Minimum Airflow (L/s)	Time of Peak Load	Maximum Heating Load (kW)	Zone Floor Area (m²)	Zone L/(s-m²)
Zone 1	2,3	204	204	Jan 1600	0,0	14,9	13,72

Zone Terminal Sizing Data

No Zone Terminal Sizing Data required for this system.

Space Loads and Airflows

Zone Name / Space Name	Mult.	Cooling Sensible (kW)	Time of Load	Air Flow (L/s)	Heating Load (kW)	Floor Area (m²)	Space L/(s-m²)
Zone 1							
JUNTA DE RECURSOS	1	2,3	Jan 1600	204	0,0	14,9	13,72

Ventilation Sizing Summary for JUNTA DE RECURSOS

Project Name: CENTRO INTEG. SEGURANÇA PÚBLICA DE HORIZONTE Rev01
 Prepared by: José Mendonça Filho Segundo
 05/09/2022 08:24

1. Summary
 Ventilation Sizing Method
 Design Ventilation Airflow Rate 45 L/s

2. Space Ventilation Analysis Table

Zone Name / Space Name	Mult.	Floor Area (m²)	Maximum Occupants	Maximum Supply Air (L/s)	Required Outdoor Air (L/s/person)	Required Outdoor Air (L/s-m²)	Required Outdoor Air (L/s)	Required Outdoor Air (% of supply)	Uncorrected Outdoor Air (L/s)
Zone 1	1	14,9	6,0	204,5	7,50	0,00	0,0	0,0	45,0
Totals (incl. Space Multipliers)				204,5					45,0



Air System Design Load Summary for JUNTA DE RECURSOS

Project Name: CENTRO INTEG, SEGURANÇA PÚBLICA DE HORIZONTErev01

05/09/2022

Prepared by: José Mendonça Filho Segundo



ZONE LOADS	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 1500			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 32,2 °C / 25,6 °C			HEATING OA DB / WB 22,2 °C / 15,6 °C		
	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	2 m²	610	-	2 m²	-	-
Wall Transmission	4 m²	143	-	4 m²	0	-
Roof Transmission	0 m²	0	-	0 m²	0	-
Window Transmission	2 m²	112	-	2 m²	0	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	15 m²	0	-	15 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	40 m²	640	-	40 m²	0	-
Overhead Lighting	238 W	190	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	250 W	250	-	0	0	-
People	6	321	361	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	0% / 0%	0	0	0%	0	0
>> Total Zone Loads	-	2265	361	-	0	0
Zone Conditioning	-	2291	361	-	0	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Return Fan Load	204 L/s	0	-	204 L/s	0	-
Ventilation Load	45 L/s	419	950	45 L/s	-60	0
Supply Fan Load	204 L/s	0	-	204 L/s	0	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	2710	1311	-	-60	0
Central Cooling Coil	-	2710	1311	-	-60	0
>> Total Conditioning	-	2710	1311	-	-60	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

Handwritten signature and initials.

Zone Sizing Summary for PERITO

Project Name: CENTRO INTEG, SEGURANÇA PÚBLICA DE HORIZONTE rev01

05/09/2022

Prepared by: José Mendonça Filho Segundo



Air System Information

Air System Name PERITO
 Equipment Class SPLT AHU
 Air System Type SZCAV

Number of zones 1
 Floor Area 11,2 m²
 Location Fortaleza, Brazil

Sizing Calculation Information

Calculation Months Jan to Dec
 Sizing Data Calculated

Zone L/s Sizing Sum of space airflow rates
 Space L/s Sizing Individual peak space loads

Zone Sizing Data

Zone Name	Maximum Cooling Sensible (kW)	Design Airflow (L/s)	Minimum Airflow (L/s)	Time of Peak Load	Maximum Heating Load (kW)	Zone Floor Area (m ²)	Zone L/(s-m ²)
Zone 1	1,8	161	161	Dec 1300	0,0	11,2	14,35

Zone Terminal Sizing Data

No Zone Terminal Sizing Data required for this system.

Space Loads and Airflows

Zone Name / Space Name	Mult.	Cooling Sensible (kW)	Time of Load	Air Flow (L/s)	Heating Load (kW)	Floor Area (m ²)	Space L/(s-m ²)
Zone 1							
PERITO	1	1,8	Dec 1300	161	0,0	11,2	14,35

Ventilation Sizing Summary for PERITO

Project Name: CENTRO INTEG, SEGURANÇA PÚBLICA DE HORIZONTE Rev01
 Prepared by: José Mendonça Filho Segundo
 05/09/2022 08:24

1. Summary
 Ventilation Sizing Method
 Design Ventilation Airflow Rate 23 L/s

2. Space Ventilation Analysis Table

Zone Name / Space Name	Mult.	Floor Area (m²)	Maximum Occupants	Maximum Supply Air (L/s)	Required Outdoor Air (L/s/person)	Required Outdoor Air (L/s-m²)	Required Outdoor Air (L/s)	Required Outdoor Air (% of supply)	Uncorrected Outdoor Air (L/s)
Zone 1	1	11.2	3.0	160.7	7.50	0.00	0.0	0.0	22.5
PERITO									22.5
Totals (incl. Space Multipliers)				160.7					22.5

Air System Design Load Summary for PERITO

Project Name: CENTRO INTEG, SEGURANÇA PÚBLICA DE HORIZONTErev01

05/09/2022

Prepared by: José Mendonça Filho Segundo



	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Dec 1400			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 31,5 °C / 25,5 °C			HEATING OA DB / WB 22,2 °C / 15,6 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	3 m²	534	-	3 m²	-	-
Wall Transmission	6 m²	270	-	6 m²	0	-
Roof Transmission	0 m²	0	-	0 m²	0	-
Window Transmission	3 m²	133	-	3 m²	0	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	11 m²	0	-	11 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	27 m²	411	-	27 m²	0	-
Overhead Lighting	179 W	140	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	180 W	180	-	0	0	-
People	3	157	180	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	0% / 0%	0	0	0%	0	0
>> Total Zone Loads	-	1825	180	-	0	0
Zone Conditioning	-	1864	180	-	0	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Return Fan Load	161 L/s	0	-	161 L/s	0	-
Ventilation Load	23 L/s	189	522	23 L/s	-30	0
Supply Fan Load	161 L/s	0	-	161 L/s	0	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	2053	702	-	-30	0
Central Cooling Coil	-	2053	702	-	-30	0
>> Total Conditioning	-	2053	702	-	-30	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

Zone Sizing Summary for RECEPÇÃO TÉRREO

Project Name: CENTRO INTEG, SEGURANÇA PÚBLICA DE HORIZONTErev01

05/09/2022

Prepared by: José Mendonça Filho Segundo



Air System Information

Air System Name **RECEPÇÃO TÉRREO**
 Equipment Class **SPLT AHU**
 Air System Type **SZCAV**

Number of zones **1**
 Floor Area **79,0 m²**
 Location **Fortaleza, Brazil**

Sizing Calculation Information

Calculation Months **Jan to Dec**
 Sizing Data **Calculated**

Zone L/s Sizing **Sum of space airflow rates**
 Space L/s Sizing **Individual peak space loads**

Zone Sizing Data

Zone Name	Maximum Cooling Sensible (kW)	Design Airflow (L/s)	Minimum Airflow (L/s)	Time of Peak Load	Maximum Heating Load (kW)	Zone Floor Area (m²)	Zone L/(s·m²)
Zone 1	37,8	3325	3325	Dec 1400	0,0	79,0	42,09

Zone Terminal Sizing Data

No Zone Terminal Sizing Data required for this system.

Space Loads and Airflows

Zone Name / Space Name	Mult.	Cooling Sensible (kW)	Time of Load	Air Flow (L/s)	Heating Load (kW)	Floor Area (m²)	Space L/(s·m²)
Zone 1							
RECEPÇÃO térreo	1	37,8	Dec 1400	3325	0,0	79,0	42,09

Ventilation Sizing Summary for RECEPÇÃO TERREO

Project Name: CENTRO INTEG, SEGURANÇA PÚBLICA DE HORIZONTErev01
 Prepared by: José Mendonça Filho Segundo

05/09/2022
 08:24

1. Summary
 Ventilation Sizing Method
 Design Ventilation Airflow Rate 329 L/s

2. Space Ventilation Analysis Table

Zone Name / Space Name	Mult.	Floor Area (m²)	Maximum Occupants	Maximum Supply Air (L/s)	Required Outdoor Air (L/s/person)	Required Outdoor Air (L/s-m²)	Required Outdoor Air (L/s)	Required Outdoor Air (% of supply)	Uncorrected Outdoor Air (L/s)
Zone 1									
RECEPÇÃO térreo	1	79,0	70,0	3324,9	4,70	0,00	0,0	0,0	329,0
Totals (incl. Space Multipliers)				3324,9					329,0



Air System Design Load Summary for RECEPÇÃO TERREO

Project Name: CENTRO INTEG, SEGURANÇA PÚBLICA DE HORIZONTErev01

05/09/2022

Prepared by: José Mendonça Filho Segundo



ZONE LOADS	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Dec 1400			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 31,5 °C / 25,5 °C			HEATING OA DB / WB 22,2 °C / 15,6 °C		
	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	140 m²	23468	-	140 m²	-	-
Wall Transmission	3 m²	138	-	3 m²	0	-
Roof Transmission	79 m²	2213	-	79 m²	0	-
Window Transmission	140 m²	6216	-	140 m²	0	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	79 m²	0	-	79 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	16 m²	242	-	16 m²	0	-
Overhead Lighting	1264 W	988	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	350 W	350	-	0	0	-
People	70	4180	5537	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	0% / 0%	0	0	0%	0	0
>> Total Zone Loads	-	37796	5537	-	0	0
Zone Conditioning	-	37936	5537	-	0	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Return Fan Load	3325 L/s	0	-	3325 L/s	0	-
Ventilation Load	329 L/s	2768	7349	329 L/s	-440	0
Supply Fan Load	3325 L/s	0	-	3325 L/s	0	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	40705	12886	-	-440	0
Central Cooling Coil	-	40705	12888	-	-440	0
>> Total Conditioning	-	40705	12888	-	-440	0
Key:	Positive values are ckg loads Negative values are htg loads			Positive values are htg loads Negative values are ckg loads		

Zone Sizing Summary for SALA DE TREINAMENTO

Project Name: CENTRO INTEG, SEGURANÇA PÚBLICA DE HORIZONTErev01

05/09/2022

Prepared by: José Mendonça Filho Segundo



Air System Information

Air System Name **SALA DE TREINAMENTO**
 Equipment Class **SPLT AHU**
 Air System Type **SZCAV**

Number of zones **1**
 Floor Area **89,8 m²**
 Location **Fortaleza, Brazil**

Sizing Calculation Information

Calculation Months **Jan to Dec**
 Sizing Data **Calculated**

Zone L/s Sizing **Sum of space airflow rates**
 Space L/s Sizing **Individual peak space loads**

Zone Sizing Data

Zone Name	Maximum Cooling Sensible (kW)	Design Airflow (L/s)	Minimum Airflow (L/s)	Time of Peak Load	Maximum Heating Load (kW)	Zone Floor Area (m²)	Zone L/(s-m²)
Zone 1	13,0	1140	1140	Feb 1500	0,0	89,8	12,69

Zone Terminal Sizing Data

No Zone Terminal Sizing Data required for this system.

Space Loads and Airflows

Zone Name / Space Name	Mult.	Cooling Sensible (kW)	Time of Load	Air Flow (L/s)	Heating Load (kW)	Floor Area (m²)	Space L/(s-m²)
Zone 1							
SALA DE TREINAMENTO	1	13,0	Feb 1500	1140	0,0	89,8	12,69

Ventilation Sizing Summary for SALA DE TREINAMENTO

Project Name: CENTRO INTEG, SEGURANÇA PÚBLICA DE HORIZONTErev01
Prepared by: José Mendonça Filho Segundo

05/09/2022

08:24

1. Summary
Ventilation Sizing Method
Design Ventilation Airflow Rate
Sum of Space OA Airflows
533 L/s

2. Space Ventilation Analysis Table

Zone Name / Space Name	Mult.	Floor Area (m²)	Maximum Occupants	Maximum Supply Air (L/s)	Required Outdoor Air (L/s/person)	Required Outdoor Air (L/s-m²)	Required Outdoor Air (L/s)	Required Outdoor Air (% of supply)	Uncorrected Outdoor Air (L/s)
Zone 1									
SALA DE TREINAMENTO	1	89,8	71,0	1139,6	7,50	0,00	0,0	0,0	532,5
Totals (incl. Space Multipliers)				1139,6					532,5

[Handwritten signature]



Air System Design Load Summary for SALA DE TREINAMENTO

Project Name: CENTRO INTEG, SEGURANÇA PÚBLICA DE HORIZONTErev01

05/09/2022

Prepared by: José Mendonça Filho Segundo



	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 1500			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 32,2 °C / 25,6 °C			HEATING OA DB / WB 22,2 °C / 15,6 °C		
ZONE LOADS	Details	Sensible (W)	Latent (W)	Details	Sensible (W)	Latent (W)
Window & Skylight Solar Loads	12 m²	2019	-	12 m²	-	-
Wall Transmission	39 m²	1267	-	39 m²	0	-
Roof Transmission	90 m²	2304	-	90 m²	0	-
Window Transmission	12 m²	596	-	12 m²	0	-
Skylight Transmission	0 m²	0	-	0 m²	0	-
Door Loads	0 m²	0	-	0 m²	0	-
Floor Transmission	90 m²	0	-	90 m²	0	-
Partitions	0 m²	0	-	0 m²	0	-
Ceiling	51 m²	825	-	51 m²	0	-
Overhead Lighting	1437 W	1144	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	1000 W	1000	-	0	0	-
People	71	3799	4266	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	0% / 0%	0	0	0%	0	0
>> Total Zone Loads	-	12953	4266	-	0	0
Zone Conditioning	-	13332	4266	-	0	0
Plenum Wall Load	0%	0	-	0	0	-
Plenum Roof Load	0%	0	-	0	0	-
Plenum Lighting Load	0%	0	-	0	0	-
Return Fan Load	1140 L/s	0	-	1140 L/s	0	-
Ventilation Load	533 L/s	4890	10375	533 L/s	-712	0
Supply Fan Load	1140 L/s	0	-	1140 L/s	0	-
Space Fan Coil Fans	-	0	-	-	0	-
Duct Heat Gain / Loss	0%	0	-	0%	0	-
>> Total System Loads	-	18222	14641	-	-712	0
Central Cooling Coil	-	18222	14642	-	-712	0
>> Total Conditioning	-	18222	14642	-	-712	0
Key:	Positive values are clg loads Negative values are htg loads			Positive values are htg loads Negative values are clg loads		

Zone Sizing Summary for SLA VIDEO MONITORAMENTO

Project Name: CENTRO INTEG, SEGURANÇA PÚBLICA DE HORIZONTE rev01

05/09/2022

Prepared by: José Mendonça Filho Segundo

FLS 640

08/24

Air System Information

Air System Name SLA VIDEO MONITORAMENTO
Equipment Class SPLT AHU
Air System Type SZCAV

Number of zones 1
Floor Area 32,8 m²
Location Fortaleza, Brazil

Sizing Calculation Information

Calculation Months Jan to Dec
Sizing Data Calculated

Zone L/s Sizing Sum of space airflow rates
Space L/s Sizing Individual peak space loads

Zone Sizing Data

Zone Name	Maximum Cooling Sensible (kW)	Design Airflow (L/s)	Minimum Airflow (L/s)	Time of Peak Load	Maximum Heating Load (kW)	Zone Floor Area (m ²)	Zone L/(s-m ²)
Zone 1	7,4	655	655	Feb 1500	0,0	32,8	19,97

Zone Terminal Sizing Data

No Zone Terminal Sizing Data required for this system.

Space Loads and Airflows

Zone Name / Space Name	Mult.	Cooling Sensible (kW)	Time of Load	Air Flow (L/s)	Heating Load (kW)	Floor Area (m ²)	Space L/(s-m ²)
Zone 1							
SLA VIDEO MONITORAMENTO	1	7,4	Feb 1500	655	0,0	32,8	19,97

Ventilation Sizing Summary for SLA VIDEO MONITORAMENTO

Project Name: CENTRO INTEG. SEGURANÇA PÚBLICA DE HORIZONTErev01

Prepared by: José Mendonça Filho Segundo

05/09/2022

08:24

1. Summary

Ventilation Sizing Method

Design Ventilation Airflow Rate

Sum of Space OA Airflows

30 L/s

2. Space Ventilation Analysis Table

Zone Name / Space Name	Mult.	Floor Area (m²)	Maximum Occupants	Maximum Supply Air (L/s)	Required Outdoor Air (L/s/person)	Required Outdoor Air (L/s-m²)	Required Outdoor Air (L/s)	Required Outdoor Air (% of supply)	Uncorrected Outdoor Air (L/s)
Zone 1									
SLA VIDEO MONITORAMENTO	1	32.8	4.0	655.1	7.50	0.00	0.0	0.0	30.0
Totals (incl. Space Multipliers)				655.1					30.0

